


TYPICAL STREET INTERSECTION WITH UTILITIES

LEGEND

CB= COMBO BOX
G= NATURAL GAS
SS= SANITARY SEWER
SD= STORM DRAIN
W= CULINARY WATER
UP= POWER
TC= TELECOMMUNICATIONS
LD= LAND DRAIN

NOTE:
1. EXACT UTILITY PLACEMENT TO BE DETERMINED BY TOWN AND UTILITY COMPANIES

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED

STANDARD STREET INTERSECTION AND UTILITY LOCATIONS

VINEYARD

STANDARD DRAWING NUMBER:	1
CAD DWG: STANDARD DRAWINGS	
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



TYPICAL STREET KNUCKLE WITH UTILITIES

LEGEND

CB= COMBO BOX
G= NATURAL GAS
SS= SANITARY SEWER
SD= STORM DRAIN
W= CULINARY WATER
UP= POWER
TC= TELECOMMUNICATIONS
LD= LAND DRAIN

NOTE:
1. EXACT UTILITY PLACEMENT TO BE DETERMINED BY TOWN AND UTILITY COMPANIES

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED


STANDARD UTILITY LOCATIONS IN KNUCKLE

VINEYARD


STANDARD DRAWING NUMBER:	2
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



MAJOR ARTERIAL (5 LANES)
96+' ROW



MINOR ARTERIAL (3 LANES)
73' ROW



MAJOR COLLECTOR (3 LANES)
88' ROW

NOTES:
1. WHEREVER POSSIBLE, CULINARY WATER LINES SHALL BE INSTALLED ON THE NORTH AND EAST SIDE OF THE CENTERLINE.
2. FIRE HYDRANT PLACEMENT: REFER TO DESIGN CRITERIA FOR PUBLIC IMPROVEMENTS SECTION 4.02 SUB-SECTION B.
3. NO CULINARY WATER LINE SMALLER THAN 8" DIA. SHALL BE INSTALLED WITHOUT APPROVAL OF TOWN ENGINEER.
4. IMPORTED GRANULAR MATERIAL, ROADBASE AND WHERE NECESSARY ASPHALT THICKNESS WILL BE DETERMINED BY PAVEMENT DESIGN.
5. REQUIRED COVER OVER UTILITY LINES ARE AS FOLLOWS:
   CULINARY WATER = 48" MINIMUM
   SANITARY SEWER = PER DESIGN
   STORM DRAIN = PER DESIGN
   TELECOMMUNICATIONS = 24" MINIMUM
   ALL OTHERS = PER UTILITY REQUIREMENTS

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	6/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED


STANDARD STREET CROSS SECTIONS AND UTILITY LOCATIONS

VINEYARD

STANDARD DRAWING NUMBER:	3
CAD DWG: STANDARD DRAWINGS	
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



MINOR COLLECTOR (2 LANES)
63' ROW



LOCAL (2 LANES)
58' ROW

NOTES:
1. WHEREVER POSSIBLE, CULINARY WATER LINES SHALL BE INSTALLED ON THE NORTH AND EAST SIDE OF THE CENTERLINE.
2. FIRE HYDRANT PLACEMENT: REFER TO DESIGN CRITERIA FOR PUBLIC IMPROVEMENTS SECTION 4.02 SUB-SECTION B.
3. NO CULINARY WATER LINE SMALLER THAN 8" DIA. SHALL BE INSTALLED WITHOUT APPROVAL OF TOWN ENGINEER.
4. IMPORTED GRANULAR MATERIAL, ROADBASE AND WHERE NECESSARY ASPHALT THICKNESS WILL BE DETERMINED BY PAVEMENT DESIGN.
5. REQUIRED COVER OVER UTILITY LINES ARE AS FOLLOWS:
   CULINARY WATER = 48" MINIMUM
   SANITARY SEWER = PER DESIGN
   STORM DRAIN = PER DESIGN
   TELECOMMUNICATIONS = 24" MINIMUM
   ALL OTHERS = PER UTILITY REQUIREMENTS

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED

STANDARD STREET CROSS SECTIONS AND UTILITY LOCATIONS

VINEYARD

STANDARD DRAWING NUMBER:	4
CAD DWG: STANDARD DRAWINGS	
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



SIDEWALK SECTION

NOTES:

1. SIDEWALK: USE APWA PLAN 231 SIDEWALK. CONTRACTION JOINTS SHALL BE PLACED EVERY 5' FOR 5' WALKS AND EVERY 6' FOR 6' WALKS. EXPANSION JOINTS SHALL BE PLACED EVERY 50' MAXIMUM.
2. CURB AND GUTTER: USE APWA PLAN 205.1 TYPE A – 30" CURB AND GUTTER UNLESS OTHERWISE AUTHORIZED BY THE CITY ENGINEER TO MATCH EXISTING.
3. MOUNTABLE CURB AND GUTTER: USE APWA PLAN 205.3 TYPE H – 30" STANDARD CURB AND GUTTER UNLESS OTHERWISE AUTHORIZED BY THE CITY ENGINEER TO MATCH EXISTING.
4. CROSS GUTTER: USE APWA PLAN 211 AND 213 6' WATERWAY UNLESS OTHERWISE AUTHORIZED BY THE CITY ENGINEER TO MATCH EXISTING.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION

NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				


VINEYARD
STAY CONNECTED


CURB, GUTTER, AND SIDEWALK

VINEYARD

STANDARD DRAWING NUMBER: 5

CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016






SECTION A-A TYPICAL CURB & GUTTER

ENLARGED: N.T.S.

STREET TYPE	LENGTH (T)
RESIDENTIAL	6"
OTHER	8"



SECTION A-A MOUNTABLE CURB

ENLARGED: N.T.S.

NOTES:
1. SLOPED AREAS AND SLOPED DRIVEWAYS SHALL HAVE A COARSE BROOM FINISH.
2. THE DRIVEWAY, AT A POINT 4' BEHIND THE SIDEWALK, SHALL BE AT LEAST 7" HIGHER THAN THE FLOWLINE OF THE GUTTER.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED


TYPICAL CURB APPROACH

VINEYARD

STANDARD DRAWING NUMBER:	6
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



BUS STOP PAD
PLAN VIEW



SECTION A-A
ENLARGED: N.T.S.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION

NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				


VINEYARD
STAY CONNECTED

TYPICAL
BUS STOP PAD

VINEYARD

STANDARD DRAWING NUMBER: 6A


CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	CRW
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016




NOTES:

1. LANDING SHALL NOT EXCEED 2% IN ANY DIRECTION

PLAN VIEW



ELEVATION




SECTION A-A


ENLARGED: N.T.S.

NOTES:

1. LANDING SHALL NOT EXCEED 2% IN ANY DIRECTION.
2. TRUNCATED DOME DETECTABLE WARNING PANEL SHALL BE CAST IRON.



DOME DETAIL



DETECTABLE WARNING PANEL

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED


STANDARD CURB RETURN AT INTERSECTION

VINEYARD


STANDARD DRAWING NUMBER:	7
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



PLAN VIEW




ELEVATION




SECTION A-A


ENLARGED: N.T.S.



MINIMUM RAMP LENGTH



DOME DETAIL



DETECTABLE WARNING PANEL

NOTES:

1. LANDING SHALL NOT EXCEED 2% IN ANY DIRECTION.
2. TRUNCATED DOME DETECTABLE WARNING PANEL SHALL BE YELLOW POLYMER COMPOSITE/FIBERGLASS.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED


PEDESTRIAN ACCESS

VINEYARD


STANDARD DRAWING NUMBER:	8
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016




PLAN VIEW



SECTION A-A



DETECTABLE WARNING PANEL



DOME DETAIL

NOTES:
1. LANDING SHALL NOT EXCEED 2% IN ANY DIRECTION.
2. TRUNCATED DOME DETECTABLE WARNING PANEL SHALL BE YELLOW POLYMER COMPOSITE/FIBERGLASS.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED


PEDESTRIAN ACCESS MID BLOCK

VINEYARD


STANDARD DRAWING NUMBER:	9
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



MULTIPLE INLET PLAN VIEW



SINGLE INLET PLAN VIEW



SECTION A-A

NOTE:
1. INSTALL "SNOUT" BMP "F" SERIES OIL-WATER-DEBRIS SEPARATOR OR APPROVED EQUIVALENT WHEN LEAVING PRIVATE DEVELOPMENT TO CITY SYSTEM.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED


STANDARD CURB FACE INLET DETAIL

VINEYARD


STANDARD DRAWING NUMBER:	10
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



MULTIPLE INLET PLAN VIEW



SINGLE INLET PLAN VIEW



SECTION A-A

NOTE:
1. INSTALL "SNOUT" BMP "F" SERIES OIL-WATER-DEBRIS SEPARATOR OR APPROVED EQUIVALENT WHEN LEAVING PRIVATE DEVELOPMENT TO CITY SYSTEM.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION

NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	CRW	DEO	9/14/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				


VINEYARD
STAY CONNECTED

MOUNTABLE CURB INLET DETAIL


VINEYARD

STANDARD DRAWING NUMBER: 11


CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	CRW
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016




SECTION A-A




LID TOP VIEW



TOP VIEW WITH FIBER REINFORCED CONCRETE COLLAR



BOX TOP VIEW



NOTE – PIPE LOCATIONS VARY

SECTION B-B

MANHOLE ACCESS CURB INLET BOX (COMBO BOX) DETAILS

NOTES:
1. MANHOLE COVER TO BE A SOLID LID CONTAINING ONE PICK HOLE. SEE SPECIFICATION DIVISION 5 FOR COVER LABEL. D&L SUPPLY P/N A-1181 (OR EQUAL).
2. FLAT LIDS SHALL BE OF ECCENTRIC DESIGN AND MEET H20 LIVE LOADING. NO FLAT RING AND COVERS WILL BE ALLOWED UNLESS APPROVED BY TOWN ENGINEER.
3. WHIRLYGIG RISER OR EQUAL SHALL BE USED INSTEAD OF GRADE RINGS TO ADJUST MANHOLE RING AND COVER TO GRADE.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED


MANHOLE ACCESS CURB INLET BOX (COMBO BOX) DETAIL

VINEYARD

STANDARD DRAWING NUMBER:	12
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



PLAN VIEW



ELEVATION SECTION

NOTES:
1. MANHOLE COVER TO BE A SOLID LID CONTAINING ONE PICK HOLE. SEE SPECIFICATION DIVISION 5 FOR COVER LABEL. D&L SUPPLY P/N A-1181 (OR EQUAL).
2. FLAT LIDS SHALL MEET H20 LIVE LOADING. NO FLAT RING AND COVERS WILL BE ALLOWED UNLESS APPROVED BY TOWN ENGINEER.
3. WHIRLYGIG RISER OR EQUAL SHALL BE USED INSTEAD OF GRADE RINGS TO ADJUST MANHOLE RING AND COVER TO GRADE.
4. 18" MAXIMUM WHIRLYGIG RISER HEIGHT.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	1/11/17
2	HANSE, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED

STORM DRAIN JUNCTION BOX DETAIL


VINEYARD

STANDARD DRAWING NUMBER:	13
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



ELEVATION SECTION

1½" MINUS MIN. GRAVEL FOUNDATION OUTSIDE SHAPE MAY BE IRREGULAR. MAXIMUM THICKNESS WILL DEPEND ON SPECIFIC SITE CONDITIONS.



SECTION A-A

NOTES:
1. MANHOLE COVER TO CONTAIN ONE PICK HOLE. SEE SPECIFICATION DIVISION 5 FOR COVER LABEL. D&L SUPPLY P/N A-1181 (OR EQUAL).
2. STEPS SHALL BE MADE OF COPOLYMER POLYPROPYLENE CONFORMING TO ASTM D-4101. REINFORCING STEEL TO BE DEFORMED ½" DIAMETER GRADE 60 ROD.
3. FLAT LIDS MAY BE USED IN LIEU OF ECCENTRIC CONES WHERE NECESSARY. FLAT LIDS SHALL BE OF ECCENTRIC DESIGN AND MEET H20 LIVE LOADING. NO FLAT RING AND COVERS WILL BE ALLOWED UNLESS APPROVED BY PUBLIC WORKS.
4. WHIRLYGIG RISER OR EQUAL SHALL BE USED INSTEAD OF GRADE RINGS TO ADJUST MANHOLE RING AND COVER TO GRADE.
5. 18" MAXIMUM RISER HEIGHT.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED

TYPICAL LAND DRAIN MANHOLE DETAIL

VINEYARD

STANDARD DRAWING NUMBER:	14
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED

STANDARD CUL-DE-SAC

VINEYARD

STANDARD DRAWING NUMBER:	15
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED


STANDARD KNUCKLE

VINEYARD


STANDARD DRAWING NUMBER:	16
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



ASPHALT SURFACE



GRAVEL SURFACE



TURF SURFACE

NOTES:
1. SLOPE TRENCH TO MEET OSHA REQUIREMENTS (LATEST EDITION) OR USE TRENCH BOX.
2. FOUNDATION AND BEDDING MATERIAL AS REQUIRED.
3. INSTALL PIPELINES ON STABLE FOUNDATION WITH UNIFORM BEARING FOR FULL LENGTH OF BARREL, EXCAVATE IN BEDDING FOR ALL PIPE JOINTS.
4. NO PATCHES WITHIN EXISTING PATCHES.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED

TYPICAL TRENCH SECTION


VINEYARD

STANDARD DRAWING NUMBER:	17
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



ELEVATION SECTION

1½" MINUS MIN. GRAVEL FOUNDATION OUTSIDE SHAPE MAY BE IRREGULAR. MAXIMUM THICKNESS WILL DEPEND ON SPECIFIC SITE CONDITIONS.



SECTION A-A

NOTES:
1. MANHOLE COVER TO CONTAIN ONE PICK HOLE. SEE SPECIFICATION DIVISION 5 FOR COVER LABEL. D&L SUPPLY P/N A-1180 VENTED (OR EQUAL).
2. STEPS SHALL BE MADE OF COPOLYMER POLYPROPYLENE CONFORMING TO ASTM D-4101. REINFORCING STEEL TO BE DEFORMED ½" DIAMETER GRADE 60 ROD.
3. FLAT LIDS MAY BE USED IN LIEU OF ECCENTRIC CONES WHERE NECESSARY. FLAT LIDS SHALL BE OF ECCENTRIC DESIGN AND MEET H20 LIVE LOADING. NO FLAT RING AND COVERS WILL BE ALLOWED UNLESS APPROVED BY PUBLIC WORKS.
4. WHIRLYGIG RISER OR EQUAL SHALL BE USED INSTEAD OF GRADE RINGS TO ADJUST MANHOLE RING AND COVER TO GRADE.
5. 18" MAXIMUM RISER HEIGHT.
6. REFER TO DESIGN CRITERIA FOR INVERT REQUIREMENTS.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED


TYPICAL SEWER MANHOLE DETAIL

VINEYARD

STANDARD DRAWING NUMBER:	18
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



PLAN VIEW



SECTION A-A

NOTES:
1. IF GRADE ALLOWS, INVERT D1 SHALL MATCH THE 0.75 DEPTH POINT OF D2. OTHERWISE, MATCH TOP OF PIPE FOR D1 TO TOP OF PIPE OF D2 AS APPROVED BY INSPECTOR.
2. AFTER ALL GRADING AROUND MANHOLE HAS BEEN COMPLETED AND FINAL SURFACING IS IN PLACE, REMOVE DEBRIS AND TEMPORARY PLUGS OR PLYWOOD FROM INSIDE OF MANHOLES.
3. IF MANHOLE IS TO BE POURED IN PLACE, FOLLOW SAME PATTERN AS SHOWN EXCEPT USE 10" MIN. WALL THICKNESS.
4. CONTACT INSPECTOR 48 HOURS (2 BUSINESS DAYS) PRIOR TO CONSTRUCTION.
5. STUBS FOR FUTURE CONNECTIONS SHALL BE PLUGGED UNTIL ACTIVATION IS APPROVED BY INSPECTOR.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED


TYPICAL MANHOLE ON EXISTING PIPE

VINEYARD

STANDARD DRAWING NUMBER:	19
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



ELEVATION SECTION



SECTION A-A

NOTES:
1. MANHOLE COVER TO CONTAIN ONE PICK HOLE. SEE SPECIFICATION DIVISION 5 FOR COVER LABEL. D&L SUPPLY P/N A-1180 VENTED (OR EQUAL).
2. STEPS SHALL BE MADE OF COPOLYMER POLYPROPYLENE CONFORMING TO ASTM D-4101. REINFORCING STEEL TO BE DEFORMED ½" DIAMETER GRADE 60 ROD.
3. FLAT LIDS MAY BE USED IN LIEU OF ECCENTRIC CONES WHERE NECESSARY. FLAT LIDS SHALL BE OF ECCENTRIC DESIGN AND MEET H20 LIVE LOADING. NO FLAT RING AND COVERS WILL BE ALLOWED UNLESS APPROVED BY PUBLIC WORKS.
4. WHIRLYGIG RISER OR EQUAL SHALL BE USED INSTEAD OF GRADE RINGS TO ADJUST MANHOLE RING AND COVER TO GRADE.
5. 18" MAXIMUM RISER HEIGHT.
6. REFER TO DESIGN CRITERIA FOR INVERT REQUIREMENTS.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	6/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED

TYPICAL SAMPLING MANHOLE


VINEYARD

STANDARD DRAWING NUMBER:	20
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



ELEVATION SECTION

1½" MINUS MIN. GRAVEL FOUNDATION OUTSIDE SHAPE MAY BE IRREGULAR. MAXIMUM THICKNESS WILL DEPEND ON SPECIFIC SITE CONDITIONS.



SECTION A-A

NOTES:
1. MANHOLE COVER TO CONTAIN ONE PICK HOLE. SEE SPECIFICATION DIVISION 5 FOR COVER LABEL. D&L SUPPLY P/N A-1180 VENTED (OR EQUAL).
2. STEPS SHALL BE MADE OF COPOLYMER POLYPROPYLENE CONFORMING TO ASTM D-4101. REINFORCING STEEL TO BE DEFORMED ½" DIAMETER GRADE 60 ROD.
3. FLAT LIDS MAY BE USED IN LIEU OF ECCENTRIC CONES WHERE NECESSARY. FLAT LIDS SHALL BE OF ECCENTRIC DESIGN AND MEET H20 LIVE LOADING. NO FLAT RING AND COVERS WILL BE ALLOWED UNLESS APPROVED BY PUBLIC WORKS.
4. USE FERNCO COUPLING TO TRANSITION TO CONCRETE OR PVC PIPE AS APPROPRIATE.
5. WHIRLYGIG RISER OR EQUAL SHALL BE USED INSTEAD OF GRADE RINGS TO ADJUST MANHOLE RING AND COVER TO GRADE.
6. 18" MAXIMUM RISER HEIGHT.
7. REFER TO DESIGN CRITERIA FOR INVERT REQUIREMENTS.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION

NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				


VINEYARD
STAY CONNECTED


TYPICAL SEWER DROP MANHOLE


VINEYARD

STANDARD DRAWING NUMBER: 21

CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016







FIRE HYDRANT & WATER VALVE

NOTES:

1. BOLTS: APPLY ONE (1) COAT OF FM2 GREASE (FOOD GRADE) TO ALL EXPOSED SURFACES OF BOLTS AND TO ALL BOLT THREADS AFTER INSTALLATION OF PIPING, FITTINGS, VALVES, AND COUPLINGS.

2. VALVES, FITTINGS, CONNECTIONS, ETC.: ENCASE ALL BURIED DUCTILE IRON VALVES, FITTINGS, CONNECTIONS AND SPECIALTIES IN MINIMUM 8 MIL. BLACK POLYETHYLENE SHEETS IN ACCORDANCE WITH AWWA C-105. SECURE POLYETHYLENE SHEETS TO THE PIPE AS SPECIFIED ABOVE.

3. DUCTILE IRON PIPE: ENCASE BURIED DUCTILE IRON PIPE IN MINIMUM 8 MIL. POLYETHYLENE SHEETS IN ACCORDANCE WITH AWWA C105 IN ALL AREAS AND SOIL TYPES AS SHOWN ON THE PROJECT PLANS OR AS SPECIFIED BY THE ENGINEER.

4. NO RISER KITS SHALL BE INSTALLED ABOVE FINISHED GRADE.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION

NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				


VINEYARD
STAY CONNECTED

FIRE HYDRANT AND WATER VALVE DETAIL


VINEYARD

STANDARD DRAWING NUMBER: 22


CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016




DEAD END PLAN VIEW




TEE PLAN VIEW




CROSS W/PLUG PLAN VIEW




VALVE ELEVATION VIEW




ELBOW PLAN VIEW




ELBOW PLAN VIEW



TEE W/PLUG PLAN VIEW



TYPICAL SECTION
THRU THRUST BLOCK



GRAVITY THRUST BLOCK
ELEVATION VIEW

NOTES:
1. THE FIGURE (100%) AT THE THRUST BLOCK INDICATES PER CENT OF TOTAL THRUST TO BE APPLIED FOR BEARING AREA.
2. THE ARROW (——→) INDICATES THRUST DIRECTION.
3. CONCRETE FOR THRUST BLOCKS TO BE 3000 P.S.I. .
4. ALL MJ AND FLANGED FITTINGS TO BE WRAPPED WITH 8 MIL POLYETHYLENE PRIOR TO PLACING CONCRETE THRUST BLOCK
5. WHERE SUFFICIENT BEARING SURFACE IS NOT AVAILABLE FOR THRUST BLOCK, MEGALUG THRUST RESTRAINING GLANDS MAY BE USED. MEGALUG THRUST RESTRAINING GLANDS SHALL BE INSTALLED PER MANUFACTURER'S RECOMENDATION INCLUDING ANY JOINT RESTRAINT. ANY USE OF MEGALUG OR CHANGE TO THE THRUST BEARING CHART MUST BE REVIEWED BY THE ENGINEER.
6. MEGALUGS OR EQUAL REQ'D AT ALL FITTING TO PIPE JOINTS.

TABLE 1

USE WHEN LINE PRESSURE AND SOIL BEARING STRENGTH ARE KNOWN.						
LINE PRESSURE: psi TEST PRESSURE (sf = 1.5): psi SOIL BEARING STRENGTH: psf (SOIL BEARING STRENGTH DETERMINED FROM A GEOTECHNICAL INVESTIGATION.)						
SIDE THRUST (lbs.) PER 1 PSI LINE PRESSURE						
PIPE SIZE (")	PIPE AREA (sq. in.)	DEAD END OR TEE (lbs.)	90° BEND (lbs.)	45° BEND (lbs.)	22.5° BEND (lbs.)	11.25° BEND (lbs.)
4	14.39	22	31	17	9	5
6	31.17	49	69	37	19	10
8	56.88	86	121	66	34	17
10	86.92	131	185	100	51	26
12	124.29	187	264	143	73	37
14	168.33	253	358	194	99	50
16	219.56	330	466	253	129	65
18	277.59	417	589	319	163	82
20	342.41	514	727	394	201	101
24	490.09	736	1040	563	287	145
30	757.69	1137	1608	870	444	223

TABLE 2

USE WHEN LINE PRESSURE AND SOIL BEARING STRENGTH ARE NOT KNOWN.						
LINE PRESSURE: 120 psi TEST PRESSURE (sf = 1.5): 180 psi SOIL BEARING STRENGTH: 1,500 psi						
AREA OF BEARING REQUIRED (sq. ft.)						
PIPE SIZE (")	PIPE AREA (sq. in.)	DEAD END OR TEE (lbs.)	90° BEND (lbs.)	45° BEND (lbs.)	22.5° BEND (lbs.)	11.25° BEND (lbs.)
4	14.39	1.7	2.4	1.3	0.7	0.3
6	31.17	3.9	5.5	3.0	1.5	0.8
8	56.88	6.8	9.7	5.2	2.7	1.3
10	86.92	10.4	14.8	8.0	4.1	2.0
12	124.29	14.9	21.1	11.4	5.8	2.9
14	168.33	20.2	28.6	15.5	7.9	4.0
16	219.56	26.3	37.3	20.2	10.3	5.2
18	277.59	33.3	47.1	25.5	13.0	6.5
20	342.41	41.1	58.1	31.4	16.0	8.1
24	490.09	58.8	83.2	45.0	22.0	11.5
30	757.69	90.9	128.6	69.6	35.5	17.8

EXAMPLE FOR TABLE 1:
8-INCH 90° BEND
LINE PRESSURE = 100 psi
FROM TABLE: THRUST PER 1 psi =121 lbs.
CALCULATE TOTAL THRUST: 100 psi x 121 lbs/psi = 12,100 lbs
SOIL BEARING STRENGTH = 2,000 psf
AREA OF BEARING REQUIRED FOR THRUST BLOCK IS 6.1 sq. ft. (12,100 lbs / 2,000 psf = 6.1 sf. ft.)

* PIPE AREA IS BASED ON LARGEST ACTUAL INSIDE DIAMETER OF DUCTILE IRON PIPE.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION

NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				


VINEYARD
STAY CONNECTED


THRUST BLOCK DETAILS

VINEYARD

STANDARD DRAWING NUMBER: 23

CAD DWG: STANDARD DRAWINGS	
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016





TAP ON PVC PIPE

NOTES:

1. ¾" – 1" METERS PROVIDED AND INSTALLED BY CITY.
   1½" – 2" METERS PROVIDED BY CITY, INSTALLED BY CONTRACTOR.
2. WATER SERVICE TO BE LOCATED PER APPROVED UTILITY PLAN.
3. ALL CONNECTIONS SHALL BE MADE USING PACK JOINTS (COMPRESSION) TYPE FITTINGS WITH INSERTS.
4. NO. 14 GAUGE COPPER TRACER WIRE REQUIRED, ATTACHED TO WIRE AT MAIN AND EXTENDED INTO METER BOX.
5. WATER METER TO BE LOCATED 2' MIN. FROM DRIVEWAYS.

TABLE

	1	2	3	4	5
METER SIZE	BADGER METER MODEL	METER BOX SIZE, ADS/HDPE WHITE	LID D&L FOUNDRY 2" HOLE *	FORD COPPERSETTERS PART # *	
¾"	M–25	21" x 36"	L–2244	VBHC7318W4444QNL	1" POLY
1"	M–70	21" x 36"	L–2244	VBHC7418W4444QNL	1" POLY
1½"	M–120	30" DIA. x 30" DEEP	B–5076 w/ PICK HOLE	VBH76181166NL	1½" POLY
2"	M–170	30" DIA. x 30" DEEP	B–5076 w/ PICK HOLE	VBH77181177NL	2" POLY

* OR EQUIVALENT UPON APPROVAL BY TOWN/CITY

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION

NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				


VINEYARD
STAY CONNECTED

TYPICAL CULINARY WATER CONNECTION


VINEYARD

STANDARD DRAWING NUMBER: 24

CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016




PLAN VIEW



ELEVATION

KEYED NOTES		
MARK	QTY	DESCRIPTION
1	1	5'-0"x10'-0" I.D. PRECAST CONCRETE VAULT
2	1	8" THK FLAT CONCRETE TOP
3	1	30"x30" ALUMINUM HATCHWAY w/ SAFETY NET, EXTEND 6" ABOVE VAULT LID IF COVERED BY LANDSCAPING
4	1	2" HOLE IN LID FOR AMR TRANSMITTER
5	2	3" FLG TEE
6	3	3" NRS GATE VALVE
7	2	3" FLG 90° ELL
8	1	3" FLG x FLG SPOOL, 54" LONG
9	1	3" FLG STRAINER
10	1	3" FLANGE COUPLING ADAPTER
11	1	3" FLG x PE SPOOL, 15" LONG
12	1	3" BADGER E-SERIES G2 ULTRASONIC METER
13	1	3" FLG x FLG SPOOL, 15" LONG
14	2	3" DI STUB-OUT
15	2	GALVANIZED ALL-THREAD RETAINER ROD
16	3	ADJUSTABLE PIPE SUPPORTS
17	1	GRAVEL BED (BY OTHERS)
18	2	ALL JOINTS MADE WATER-TIGHT WITH PLASTIC FLEXIBLE GASKET (RAMNEK)
19	2	PIPE PENETRATION FILLED w/ NON-SHRINK GROUT
20	1	NAMEPLATE INDICATING: MFG: NUMBER: MODEL: DATE MANUFACTURED
21	7	MANHOLE STEPS
22	2	1" PVC PIPE FOR TRACER WIRE (TRACER WIRE PROVIDED BY OTHERS)
23	–	NOT USED
24	–	NOT USED
25	1	12"x12"x3" DEEP SUMP w/ CAST IRON GRATE (OPTIONAL KNOCKOUT TO DRAIN)



NAMEPLATE

SPECIFICATIONS

CONCRETE:

CLASS I/II CONCRETE WITH DESIGN STRENGTH OF 5000 PSI AT 28 DAYS. UNIT IS OF MONOLITHIC CONSTRUCTION AT FLOOR AND FIRST STAGE OF WALL WITH SECTIONAL RISER TO REQUIRED DEPTH. COMBINED ASSEMBLY WEIGHT OF APPROXIMATELY 46,000 LBS.

REINFORCEMENT:

GRADE 60 REINFORCED. STEEL REBAR CONFORMING TO ASTM A615 ON REQUIRED CENTERS OR EQUAL. BAR BENDING & PLACEMENT SHALL COMPLY WITH THE LATEST ACI STANDARDS FOR PRECAST CONCRETE. LIFTING INSERTS SHALL BE INSTALLED PER MANUFACTURER'S REQUIREMENTS.

HATCHWAY:

¼" ALUMINUM DIAMOND PLATE COVER, WITH ¼" EXTRUDED ALUMINUM FRAME. HATCH TO BE FURNISHED WITH 316 STAINLESS STEEL SNAP LOCK & BRASS HINGES.

ENGINEERING DATA:

FIELD EXCAVATION AND PREPARATION SHALL BE COMPLETED PRIOR TO DELIVERY OF ASSEMBLY. USE DIMENSIONAL DATA AS SHOWN. PIPE, VALVES AND FITTING OF THE ASSEMBLY ARE APPROVED BY ONE OR MORE OF THE FOLLOWING ASSOCIATIONS

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION

NO.	DESCRIPTION	BY	APR.	DATE
1	HANSEN, ALLEN & LUCE	URH	CMT	9/12/25
2				
3				
4				

VINEYARD
STAY CONNECTED

LARGE METER ASSEMBLY

VINEYARD


STANDARD DRAWING NUMBER:	25
CAD DWG: STANDARD DRAWINGS	
PLOT SCALE:	1.000
DRAWN BY:	
DESIGN BY:	
CHECKED BY:	
ADOPTED DATE:	

LIST OF MATERIALS


ITEM	QTY	SIZE	DESCRIPTION
1	1	A x B	MJ x FE DUCTILE IRON REDUCER
2	1	B x AS REQ'D	FLG x FLG DUCTILE IRON SPOOL
3	2	B x B	FLG x FLG DUCTILE IRON TEE
4	3	B	FLG x FLG GATE VALVE
5	1	B	BADGERMETER FSAA-01 FIRE SERIES METER W/SIZE ON SIZE BYPASS
6	1	B	DRESSER FLANGED ADAPTER STYLE 128
7	2	C x AS REQ'D	FLG x PE DUCTILE IRON PIPE
8	1	B	FEBCO MODEL LF880V (UP TO 8") OR FEBCO MODEL LF860V (FOR 10") OR EQUAL
9	1	C	FEBCO SERIES 611 VALVE SETTERS MJ x FLG OR EQUAL
10	2	B x 12"	FLG x FLG DUCTILE IRON SPOOL
11	2	B	FLG x FLG DUCTILE IRON 90° ELBOW
12	1	B x AS REQ'D	FLG x PE DUCTILE IRON PIPE W/ ALL THREAD
13	1	A x C	MJ x FLG DUCTILE IRON REDUCER
14	1	B x C	MJ x FLG DUCTILE IRON REDUCER
15	2	A	FLG x MJ C900 FLANGE ADAPTOR
16	1	ENCLOSURE	SAFE-T-COVER MODEL # 1000LU880-AL (UP TO 8") (OR EQUAL) SAFE-T-COVER MODEL # 1000-AL (10") (OR EQUAL)
17	1	VAULT	PRECAST VAULT SIZE SHALL MEET MINIMUM CLEARANCE REQ'D
18	1	30"	MANHOLE RING & COVER D&L SUPPLY # A-1181 W/ 6" GRADE RING
19	1	HEATER	SAFE-T-COVER MODEL NO. HCH2000-120 (OR EQUAL)

NOTE: ALL DUCTILE IRON PIPE AND FITTINGS TO BE POLYWRAPPED.


"A" = MAIN LINE SIZE.
"B" = REQ'D METER SIZE.
"C" = SIZE BACKFLOW ASSEMBLY TO MATCH METER FLOW (CFS).



BACKFLOW PREVENTION ASSEMBLY ENCLOSURES



SECTION B-B



SECTION C-C

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION

NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	6/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				


VINEYARD
STAY CONNECTED

BACKFLOW PREVENTION ASSEMBLY

VINEYARD

STANDARD DRAWING NUMBER: 26


CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



STUB FOR NEW CONSTRUCTION

NOTES FOR CONNECTING TO NEW SEWER MAIN:

1. CONNECTION TO MAIN SHALL BE BY WYE'S OR TEE'S INSTALLED AS PART OF THE SEWER MAIN CONSTRUCTION.
2. LOCATION OF STUB TO BE LOCATED PER APPROVED UTILITY PLAN.
3. SHOW CENTERLINE STATION OF THE LATERAL FROM THE NEAREST DOWNSTREAM MANHOLE. USE SAME STATIONING USED FOR SEWER MAIN.
4. TRAFFIC RATED CLEANOUT LID REQ'D IF LOCATED IN TRAFFIC AREAS.



TIE TO EXISTING CONSTRUCTION

NOTES FOR CONNECTING TO EXISTING SEWER MAIN:

1. CONNECTION TO BE MADE IN PRESENCE OF PUBLIC WORKS INSPECTOR.
2. INSERTA-TEE OR EQUAL INSTALLED PER MANUFACTURER RECOMMENDATIONS.
3. TRAFFIC RATED CLEANOUT LID REQ'D IF LOCATED IN TRAFFIC AREAS.
4. CLEAN-OUTS REQUIRED AT PROPERTY LINE, EVERY 100' FOR 6" SERVICES AND 50' FOR 4" SERVICES AND AT EVERY COMBINATION OF BEND TOTALING 90°.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	LRH	CMT	9/12/25
3				
4				


VINEYARD
STAY CONNECTED

TYPICAL
SEWER LATERAL

VINEYARD

STANDARD DRAWING NUMBER:	27
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016





REFER TO LATEST TIMPANOGOS SPECIAL SERVICE DISTRICT (TSSD) WASTEWATER COLLECTION SYSTEM STANDARDS AND SPECIFICATIONS FOR GREASE TRAP SIZING AND DETAILS

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED

TYPICAL
GREASE TRAP

VINEYARD

STANDARD DRAWING NUMBER:	28
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	
ADOPTED DATE:	SEPTEMBER 1, 2016



NOTES:

1. ACCESSIBLE PARKING SPACES MUST BE LOCATED ON THE SHORTEST ROUTE OF TRAVEL TO AN ACCESSIBLE FACILITY ENTRANCE.
2. DESIGNATED RESERVED SIGN BY EACH SPACE.
3. EACH PARKING LOT SHALL HAVE A MINIMUM OF ONE (1) "VAN ACCESSIBLE" SPACE
4. ONE IN EVERY EIGHT (8) ACCESSIBLE SPACES SHALL HAVE AN ACCESS AISLE 8'-0" WIDE AND SHALL BE SIGNED " VAN ACCESSIBLE".
5. SIGNS SHALL HAVE THE "ACCESSIBLE SYMBOL" WITH "VAN ACCESSIBLE" INDICATED BELOW.
6. RAMP MAXIMUM SLOPE 12:1.
7. OTHER AS REQUIRED BY ADA STANDARDS.

MINIMUM NUMBER OF ACCESSIBLE PARKING SPACES
ADA STANDARD FOR ACCESSIBLE DESIGN 4.1.2(5)

TOTAL NUMBER OF PARKING SPACES PROVIDED (PER LOT)	TOTAL MINIMUM NUMBER OF ACCESSIBLE PARKING SPACES (60" & 96" AISLES	VAN ACCESSIBLE PARKING SPACES WITH MIN. 96" WIDE ACCESS AISLE	ACCESSIBLE PARKING SPACES WITH MIN. 60" WIDE ACCESS AISLE
1 TO 25	COLUMN A 1	1	0
26 TO 50	2	1	1
51 TO 75	3	1	2
76 TO 100	4	1	3
101 TO 150	5	1	4
151 TO 200	6	1	5
201 TO 300	7	1	6
301 TO 400	8	1	7
401 TO 500	9	2	7
501 TO 1000	2% OF TOTAL PARKING PROVIDED IN EACH LOT	1/8 OF COLUMN A *	7/8 OF COLUMN A **
1001 AND OVER	20 PLUS 1 FOR EACH 100 OVER 1000	1/8 OF COLUMN A *	7/8 OF COLUMN A **

* ONE OUT OF EVERY ACCESSIBLE SPACES ** 7 OUT OF EVERY 8 ACCESSIBLE PARKING SPACES

STATEMENT OF USE
THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVIATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	1/26/18
2	HANSEN, ALLEN & LUCE	DOL	CRW	9/12/28
3				
4				
5				


REVISION

VINEYARD
STAY CONNECTED

ADA PARKING AND PASSENGER LOADING ZONE

VINEYARD

STANDARD DRAWING NUMBER:	29
CAD DWG STANDARD DRAWINGS	
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



RIGHT ANGLE PARKING




PARALLEL PARKING



30 DEGREE ANGLE PARKING
MUST HAVE 20' TRAVEL LANE FOR 2 WAY TRAFFIC

45 DEGREE ANGLE PARKING
MUST HAVE 22' TRAVEL LANE FOR 2 WAY TRAFFIC



60 DEGREE ANGLE PARKING
MUST HAVE 24' TRAVEL LANE FOR 2 WAY TRAFFIC

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION

NO.	DESCRIPTION	BY	APR.	DATE
1	HANSEN, ALLEN & LUCE	URH	CWT	9/12/25
2				
3				
4				


VINEYARD
STAY CONNECTED

PARKING LOT


VINEYARD

STANDARD DRAWING NUMBER: 30A


CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	
DESIGN BY:	
CHECKED BY:	
ADOPTED DATE:	



DRIVEWAY WIDTHS



MINIMUM TURNING RADIUS



PARKING STRUCTURE

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION

NO.	DESCRIPTION	BY	APR.	DATE
1	HANSEN, ALLEN & LUCE	URH	CMT	9/12/25
2				
3				
4				


VINEYARD
STAY CONNECTED

PARKING LOT

VINEYARD

STANDARD DRAWING NUMBER: 30B

CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	
DESIGN BY:	
CHECKED BY:	
ADOPTED DATE:	



HALF CROSS SECTION

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	LRH	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED


110-FOOT ROUNDABOUT FOR LOCAL STREET INTERSECTION

VINEYARD


STANDARD DRAWING NUMBER:	31
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



STREET SIGN ON LIGHT POLE INSTALLATION DETAIL



TYPICAL STREET/STOP SIGN INSTALLATION



TYPICAL STREET/STOP SIGN LOCATION PLAN VIEW

NOTES:
1. STREET SIGNS SHALL BE INSTALLED ON LIGHT POLES OR ABOVE STOP SIGNS. IF THE STREET HAS A NAME, THE NAME SHALL BE PLACED ABOVE AND THE NUMBER UNDERNEATH.
2. SIGN POSTS SHALL BE "TELESPAR" OR EQUAL 2" SQUARE TUBING MANUFACTURED PRODUCTS INSTALLED IN V-LOC BREAK AWAY ANCHORS.
3. ALL REGULATORY SIGN SHALL BE SIZED AND INSTALLED PER CURRENT MUTCD STANDARDS.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED

TYPICAL STREET / STOP SIGN INSTALLATION DETAIL

VINEYARD

STANDARD DRAWING NUMBER:	32
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



NOTES:

1. SUPPLIED BY HOLOPHANE OR EQUIVALENT.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED

TYPICAL STREET LIGHT 1

VINEYARD

STANDARD DRAWING NUMBER:	33
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



NOTES:

1. SUPPLIED BY HOLOPHANE OR EQUIVALENT.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED

TYPICAL STREET LIGHT 2

VINEYARD

STANDARD DRAWING NUMBER:	34
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



NOTES:

1. SUPPLIED BY HOLOPHANE OR EQUIVALENT.

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION

NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				


VINEYARD
STAY CONNECTED

TYPICAL STREET LIGHT 3

VINEYARD


STANDARD DRAWING NUMBER: 35

CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016




BOTTOM VIEW

(INDICATED POLE IS LAYING DOWN WITH ACCESS COVER FACING UP)



CONCRETE POLE BASE TYPE A

CONCRETE BASE FOR TYPICAL STREET LIGHT 1 AND 2



CONCRETE POLE BASE TYPE B

CONCRETE BASE FOR TYPICAL STREET LIGHT 3

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION


NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED

CONCRETE POLE BASE (STREET LIGHT)

VINEYARD

STANDARD DRAWING NUMBER:	36
CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016



4" FOUNDATION DRAIN DETAIL

STATEMENT OF USE

THIS DOCUMENT AND ANY ILLUSTRATIONS HEREON ARE PROVIDED AS STANDARD CONSTRUCTION DETAILS WITHIN THE TOWN OF VINEYARD. DEVEATION FROM THIS DOCUMENT REQUIRES APPROVAL FROM THE TOWN OF VINEYARD. THE TOWN OF VINEYARD CORPORATION CAN NOT BE HELD LIABLE FOR MISUSE OR CHANGES REGARDING THIS DOCUMENT.

REVISION

NO.	DESCRIPTION	BY	APR.	DATE
1	STANDARDS UPDATE	JMM	DEO	8/08/16
2	HANSEN, ALLEN & LUCE	DCL	CMT	9/12/25
3				
4				

VINEYARD
STAY CONNECTED

4-INCH FOUNDATION DRAIN DETAIL

VINEYARD

STANDARD DRAWING NUMBER: 37

CAD DWG:	STANDARD DRAWINGS
PLOT SCALE:	1.000
DRAWN BY:	JMM
DESIGN BY:	CRW
CHECKED BY:	DEO
ADOPTED DATE:	SEPTEMBER 1, 2016